



NEW EZ BATCH III

WIRING TERMINAL DESIGNATION
 GROUND TERMINAL NOTE GROUNDING IS REQUIRED
 FUSE 5 AMP L1 OPERATING POWER (INPUT)
 FUSE 0.5 AMP L1 OPERATING POWER TO ON/OFF BUTTON
 1 L1 POWER TERMINAL 5AMP
 1 L1 POWER TERMINAL 5AMP
 1 L1 POWER TERMINAL 5AMP
 2 L2 OPERATING POWER (INPUT)
 2 L2 NEUTRAL TERMINAL
 2 L2 NEUTRAL TERMINAL
 3 CR1 RELAY SPDT 5 AMP 120/240VAC
 N/O OUTPUT
 COMMON INPUT
 N/C OUTPUT
 4 CR2 RELAY SPDT 5 AMP 120/240VAC
 N/O OUTPUT
 COMMON INPUT
 N/C OUTPUT
 11 +12-24VDC OUTPUT
 12 -12-24VDC OUTPUT
 13 PULSE OR FREQUENCY INPUT

	1963 ESSEX COURT REDLANDS, CA 92373 (909) 307-2295 (909) 307-2395 fax	WIRING DIAGRAM EZ BATCH III		Approved By: Drawing I.D.	Date: 01/22/2013
			Origin: Rev. a	Rev. b	
			Scale: 3/4" = 1" Drawn By:		